

Insulated Shipping Container Liner Assembly Instructions

1. Check all parts are present:
 - 2 side wall panels
 - 2 ceiling panel
 - 1 roll of joining tape
 - Floor liner (if included)
2. Make sure that the walls, roof, and floor on the inside of the container are completely dry and clean. This can be done with a brush.
3. Take one wall section and start fixing the liner from the centre of the back wall then make your way forward until you get to the front door. Do **NOT** press the sheet into the corrugations, these help to insulate.
4. Repeat step 2 on the other walls.
5. Insulate the roof, this arrives in two rolls for ease of installation.
6. If a floor liner is included, finish by insulating the floor.
7. Make sure all edges and joints are completely sealed with the added silver foil joining tape.
8. Use a brush and press onto the liner to ensure it is fixed and secure on the wall.
9. You should now have a fully insulated shipping container.



Kingfisher Direct Ltd

Randall Park Way, Hallcroft, Retford, Nottinghamshire, DN227WF

Tel. 01777 858009 Company Number: 07752788 VAT Number: 120941249